

Visual Guidance Research & Development

Update

Given by: Lauren Vitagliano

**IESALC Spring meeting May 8, 2014
Washington, DC**



**Federal Aviation
Administration**



TOPICS

1. **Airport Linear Source Visual Aid**
2. **Frangible Connections and Structures**
3. **Electrical Infrastructure Research**
4. **Constant Current Regulator Loading**
5. **Safety Orange Visual Aids for Airport Construction**
6. **Enhanced Visual Aids for EMAS**
7. **RSA/Approach Hold Signs and Markings**


Airport Linear Source Visual Aid




Experiment 1 Stimuli – “No Noise”

- Linear element spacing: 50, 100, 200 ft
- Linear element length: 2, 8, 32 ft
- Configurations: 90° (low-speed taxiway exit) and 30° (high-speed taxiway exit), left and right


30° Left



90° Left




30° Right




Experiment 1 Results – **No Noise**

Accuracy was always > 90%




Experiment 2 Stimuli – Visual Noise




Experiment 3 - Dynamic

- Dynamic animation starting from 2000 ft away, 50 mph
- 30°/90° left/right taxiway from runway
- Centerline delineation (white/runway, green/taxiway)
- 2, 8 or 32 ft element length; 50, 100, 200 ft spacing





Experiment 4 – Lower Intensity

- Same as experiment 3 except luminance was decreased to:
- White 30 cd/m²
 - Green 18 cd/m²
 - Blue 1.8 cd/m²
 - Background 0.25 cd/m²



Experiment 2 to 4 Results


**Same correlation between
Length and Spacing to Reaction
Time in all experiments**



**Correlated
($r^2=0.69$) to
Experiment 1 & 2
results**

Factor: 8.8x

Developed Predictive Response Time Equation



$$RT \text{ (ms)} = 286 - 607 \log L + 989 \log S$$

Combinations of delineation element length and spacing to achieve the same relative response times expected from 2-ft-long delineation elements spaced at 50 ft and 100 ft.

Base Case 1	Element length	2 ft	6.2 ft	12.0 ft	19.2 ft
	Element spacing	50 ft	100 ft	150 ft	200 ft
	Relative response time	1784 ms	1784 ms	1784 ms	1784 ms
Base Case 2	Element length	2 ft	3.9 ft	6.2 ft	
	Element spacing	100 ft	150 ft	200 ft	
	Relative response time	2081 ms	2081 ms	2081 ms	

Validation Study

- ➔ Validation study was conducted using the **9 linear segments** created with **blue and green LED** sources.
- ➔ For the experiment, **prototype** linear light source segments in **2-ft, 4-ft, and 8-ft lengths** were used at a **25-ft and 100-ft spacing**.
- ➔ The experiment was conducted in a large and enclosed space where the ambient illumination could be turned off.
- ➔ The **results** were **consistent with the laboratory experiments** using computer displayed images.

Validation Study



View of one of the test conditions as presented to observers that participated in the validation field experiment.

PHASE THREE




- ➔ **Task 1: Conduct a simulation evaluation. (4 months)**
 - Utilizing the FAA Technical Center's Simulation facility.



PHASE THREE

➔ Task 2: Conduct a field evaluation. (6 months)

- Utilizing the **P**artnership to **E**nhance **G**eneral **A**viation **S**afety, **A**ccessibility and **S**ustainability (**PEGASAS**) Center of Excellence.
- **Three** of the six core members also **own and operate their own airports** (Purdue, Ohio State, Texas A&M).



Schedule

Activity	Completion
Test Plan	02/28/12
Phase 1	09/30/12
Analysis/Decision Point	10/31/12
Phase 2	02/15/13
Analysis/Decision Point	02/27/13
Extended Phase 2	07/31/13
Phase 3	06/30/15
Final Report to Sponsor	09/30/15

Frangible Connections and Structures



Research on Frangible Connections and Structures

Project Objective:

Develop a better methodology for measuring and evaluating the frangibility characteristics of connections/structures intended for use on airport RSAs and TSAs.

Goal:

- **Simplified and standardized testing procedures**
- **Identify potential areas that require clarification**

Frangible Structures

Prioritized Listing of Airfield Structures for Simulation, Testing, and Analysis:

- FAA Approved Approach Lighting Systems
- Frangible Configuration of the End Fire Glide Slopes (EFGS)
- Composite Jet Blast Deflectors
- ILS localizer Array
- Small Monopole Structures (Wind Cone, Anemometer)
- PAPIs and REILs
- Airfield Signs



Types of Frangible Connections



Application of Fuse Bolts




Examples of Frangible Couplings

Research on Frangible Connections and Structures

Phase I:

- Task 1 Requirements Analysis ← **Completed**
- **Task 2 Finite Element Development** ← **On-going**
- **Task 3 Test Setup Development** ← **On-going**

For Simulation:



Research on Frangible Connections and Structures

Phase II:

- **Task 4 Test Plans / Procedures Development**
- **Task 5 Test Setup Fabrication**
- **Task 6 Dynamic Testing and Evaluation**
- **Task 7 Guidebook Development**

Electrical Infrastructure Research



Issues resulting from LED implementation in the Current **6.6A** Series Airfield Lighting System

- Added **complexity** and **cost** to the LED fixture due to the addition of electronics to mimic the **non-linear** dimming curve of incandescent lighting.
- LEDs must convert the supplied AC current to a DC current of **lower amplitude** at the array.

Electrical Test Goals

- **Characterize each system's electrical performance**
- **Characteristics will be analyzed for the development of report**
- **Electrical measurements include power consumption analysis, efficiency of the system, harmonics and electrical emissions**
- **Fixture level testing includes power analysis at each fixture**

EIRT Testing Team

Recommended Two Paths

→ Path # 1:

- **Fixture Centric**

- An airfield lighting architecture where the **fixture controls its intensity**

→ Path # 2:

- **Vault Centric**

- An airfield lighting architecture that **directly controls the fixture intensity from the power source in the vault (same as the traditional 6.6 amp)**

Architectures Tested

VAULT CENTRIC ARCHITECTURE



VAULT CENTRIC ARCHITECTURE



FIXTURE CENTRIC ARCHITECTURE



FIXTURE CENTRIC ARCHITECTURE



Roadmap Testing Phase

→ **Alpha testing at FAATC, May 2014**

- Integration including mixing of product
- Fixtures will be instrumented and monitored by FAA equipment to determine performance
- Identify any deficiencies, or adjustments to be made

→ **Beta testing at PEGASAS Airport July, 2014**

- Similar set up as alpha testing
- Large circuit
- Legacy mode will be available in case there is an issue with the circuit

Investigation of Maximum Constant Current Regulator Loading



Project Objectives

- Investigate reports of overloaded CCRs relating to a predominance of constant Volt-Amperes (VA) sign
- Investigate if restrictive maximum loading at lower steps for CCRs is specific for a particular CCR technology
- Determine any relationship between lower step loading and the use of Light Emitting Diode (LED) fixtures
- Determine if the lighting system power factor has an adverse effect upon the CCR
- Investigate the impact on power factor and input power when CCRs are under loaded.

Test Locations

- ➔ **Louis Armstrong New Orleans International Airport (MSY), New Orleans, LA**
- ➔ **George Bush Intercontinental/Houston Airport (IAH), Houston, TX**
- ➔ **Ryan Field Airport (RYN), Tucson, AZ**

Schedule

Event/Deliverable	Tentative Completion Dates
Airport Circuit Investigation/Testing	April 4, 2014
FAATC Post Investigation/Testing	July 31, 2014
Analysis/Draft Report	August 29, 2014
Final Report/Recommendations	November 15, 2014

Safety Orange Visual Aids during Airport Construction



Safety Orange Visual Aids during Airport Construction

Project Objective:

To produce measures to reduce the number of runway incursions and accidents that might be caused due to construction.

- FAA is working with Air Traffic Organization Airport Construction Advisory Council (ACAC) on this project



Visual Aids and Markings used during Construction

Current Visual Aids



Scope of Work

- **Collect data from existing construction sites**
- **Develop alternative sign and portable/reflective visual aids**
- **Simulation**
- **Field Installation and Evaluation – PVD, ISP, SFB, PDX, & ORD**



Field Installations at PDX



Findings

- ➔ **“CONSTRUCTION AHEAD” sign - 109 respondents**
 - **87% sign was conspicuous.**
 - **88% sign was comprehensible at an adequate distance.**
 - **90% sign adequately notified them of the existing construction.**

- ➔ **“CONSTRUCTION ON RAMP” sign - 51 respondents**
 - ➔ **92% sign was conspicuous.**
 - ➔ **88% sign was comprehensible at an adequate distance.**
 - ➔ **94% sign adequately notified them of the existing construction.**

- ➔ **Currently conducting additional research on TORA sign**



Enhanced Visual Aids for EMAS



Enhanced Visual Aids for EMAS



Project Objective: Determine if additional EMAS visual aids are required for pilot awareness



- Determine if additional EMAS visual aids are required for preventing inadvertent vehicle and aircraft entry

Enhanced Visual Aids for EMAS

- Surveyed 42 airports with 63 EMAS beds
 - Incidents
 - Existing markers in place
- Surveyed 399 pilots
- Input from SMEs (EMAS Manufacturer, Airport Certification Inspectors)



Current EMAS Markings/Signage



Scope of Work

- **Simulations**
- **Field Evaluations**
- **Field Installations**



Enhanced Visual Aids for EMAS

- **Recommendations**

- Red, retroreflective markers, 18” or 24” in height, spaced 7.5’ apart around the sides and rear of EMAS.
- Yellow, retroreflective markers, 18” or 24” in height, spaced 7.5’ apart along the front of EMAS.
- Engineering brief with specifications under development
- Additional research for signage – currently ongoing


APCH Hold/RSA Signage & Marking

APCH Hold/RSA Signage & Marking:

There are inconsistencies in implementing approach hold signs, marking and procedures among the nation's airports, causing confusion among ATC, pilots, airport operators and cert inspectors.

Project Objective: Install and test new signs and markings as recommended in the Safety Risk Management Document (SRMD) from the Approach Hold Workgroup to protect other critical surfaces like RSA, approach, departure, etc.


Current Configuration



08/16/2010

AC/150/5340-18F

The Problems:

Using  with **15-APCH** can result in pilot confusion.

"Do I have to hold short?"

Pilots expect  to be near the runway entrance. Results in confusion when it's a long distance from the runway.

"Why am I holding short so far from the runway?"

Having only one runway designation on the sign, **15-APCH** causes confusion when the APCH hold is being used for protecting DEP traffic.

"I don't need to hold short since RWY 15 isn't being used?"

Requiring ATC Clearances to pass a holding marking when runway not active will increase ATC workload.


No standard marking/signage for RSAs that intersect runways



Federal Aviation
Administration

Proposed Configuration

FIGURE 2-2. UPDATES TO AC 150/5340-18F, FIGURE 3




Size 3, 2 Mod, 10" Legend

**15L APCH -
33R DEP**

Example: ORD 9R APCH



Example: CLE




Scope of Work

- **Prototype Testing**



- **Simulations**



- **Field Testing / Evaluations**

- ORD, CLE, BNA, DEN

Questions/Comments?

Airport Linear Source Visual Aid - Donald Gallagher

Donald.gallagher@faa.gov, 609-485-4583

Frangible Connections and Structures – Joseph Breen

Joseph.breen@faa.gov, 609-485-8825

Questions/Comments?

Electrical Infrastructure Research

Constant Current Regulator Loading

Safety Orange Visual Aids for Airport Construction

Robert Bassey, robert.bassey@faa.gov, 609-485-5816

Enhanced Visual Aids for EMAS

RSA/Approach Hold Signs and Markings

Lauren Vitagliano, lauren.vitagliano@faa.gov, 609-485-8198