


Illuminating Engineering Society (IES) Government Contacts Sub-Committee Meeting

Steve McArthur

Visual Guidance Lighting Systems

AJM-3220

October 7, 2021



Overview

- **Visual Guidance Lighting Systems (VGLS) Team**
- **Lighting Systems and Ancillary Equipment**
- **Capital Investment Programs**
- **Active Procurements**
- **Next Generation Lighting Systems**
- **Specification and Standard Installation Drawing Updates**
- **Procurement Opportunities**



VGLS Team Contact Information

| Name | Projects | Phone |
|-----------------|--------------------------------|--------------|
| Steve McArthur | Manager | 202.253.9862 |
| Renee Williams | RVR, LIR | 202.267.9923 |
| Ndubuisi Nnorom | ALSF-2, RLMS, REIL, RRCS, SFSB | 202.267.9923 |
| Donald Lampkins | MALSR, PAPI, LED | 202.267.7332 |



Lighting Systems and Ancillary Equipment

- **High Intensity Approach Lighting System with Sequenced Flashing Lights (ALSF-2)**
- **Medium Intensity Approach Lighting System with Runway Alignment Indicator Lights (MALSR)**
- **Precision Approach Path Indicator (PAPI)**
- **Runway Visual Range (RVR)**
- **Runway End Identifier Lights (REILs)**
- **Radio Remote Control System (RRCS)**
- **Visual Approach Slope Indicator (VASI)**
- **Radio Remote Control Interface Unit (RRCIU)**
- **Replacement Lamp Monitoring System (RLMS)**
- **Lead-in Lights**
- **Semiflush Flashers and Steady Burners**
- **Low Impact Resistant (LIR) Structures**
- **Transformers**
- **Frangible Bolts**

Capital Investment Programs

- **Runway Visual Range**

Replaces older RVR equipment with PC-Based RVR equipment. RVR provides air traffic controllers with a measurement of the visibility at key points along a runway: touchdown, midpoint and rollout.

- **Approach Lighting System Safety Enhancement**

Upgrades the equipment to current standards and reduces the potential severity of take-off and landing accidents by replacing rigid structures, and the entire approach lighting system, with lightweight and low-impact structures that collapse or break apart upon impact. In addition, the program will transition to Light-Emitting Diode (LED) technology and start installations of Parabolic Aluminized Reflector (PAR) LEDs in FY 2023.

Capital Investment Programs

- **Nav aids Sustainment**

Sustains Approach Lighting Systems (ALS), which includes MALSR for Category I approaches and ALSF-2 for Category II/III approaches. Additionally, Nav aids Sustainment supports the REIL and RLMS projects.

- **Visual Nav aids for New Qualifiers (VNNQ)**

Supports the procurement, installation, and commissioning of PAPI systems and REIL systems at new qualifying runways.

Capital Investment Programs

- **Replace VASI with PAPI**

Supports the procurement, installation, and commissioning of PAPI systems in order to comply with ICAO's recommendation to replace the VASI lights with PAPI lights.

- **Instrument Landing Systems**

Supports the installation of ILS and/or High Intensity Approach Lighting System. An ILS precision approach system is comprised of a grouping of electronic devices Localizer, Glide Slope, marker beacons and, in some cases, ancillary aids (DME, ALS, RVR, etc.)

Next Generation Lighting Systems

LED PAPI / LED MALSR




LED PAPI Project


- **Objective:** The primary objective is to fully deploy LED PAPI by using the System Development, Deployment and Implementation phases of FAA's Acquisition Management Systems (AMS) process

- **Project Activities**

- Preliminary Design Review
- Critical Design Review
- Design Qualification Test
- Operational Test
- Configuration Audits
- Product Baseline
- **In-Service Management**



- **Installed and Commissioned 59 LED PAPI systems**
- **LED PAPI's have been shown to reduce energy consumption by over 60%**



LED MALSR Project



- **Issue:**
 - FAA has experienced a shortage of suppliers of the PAR-38 incandescent lamps for the MALSR systems in the NAS
- **Status:**
 - In the interim, Alternative Incandescent Lamps (AILs) have been identified and approved to support the MALSR systems in the NAS
 - Currently maintaining a pulse on the incandescent market, and procuring incandescent lamps as needed
 - A roadmap has been established to transition from current PAR-38 and PAR-56 incandescent lamps, to an energy efficient LED solution

Roadmap to the Future

- **Transition from current PAR-38 and PAR-56 incandescent lamps to energy efficient LED technology**
 - Developed alternative LED lamps that can use existing lamp fixtures to minimize cost of conversion
 - Established and execute the transition plan to replace incandescent lamps
 - Rely on LED technology to improve reliability and maintainability and reduce ops costs




LED Project Activities

- Installed LED PAR-38s at Savannah/Hilton Head Airport (SAV)
- Conducted Duration Testing at Joint Base Cape Cod (JBCC) in IFR conditions using EVFS and Natural cameras
- Completed environmental testing, including EMI, of LED PAR-56 Prototype at certified laboratory
- **Install prototype LED PAR-38s and PAR-56s at four (4) MALSR operational sites**
- **Complete and approve LED Lamp Specification**
- **Award LED Lamp production contract**

MALSR Sustainment Study

- **Determine the feasibility for continuing over 900 MALSR/MALSF/MALS systems through the year 2045**
- **Identify parts obsolescence, performance issues, parts demand, operations costs, equipment condition, system availability, characterize system supportability, and evaluate failure rate**
- **Conduct Quantitative Analysis**
- **Conduct Qualitative Analysis**
- **Develop Recommendations for Sustainment Initiatives**

[illegible]

Specification Updates

- **LED REIL:** *Approved (Mar 2018)*
- **ALSF-2 SLEP:** *Anticipated Approval (October 2021)*
- **LED PAR-38 & PAR-56 Lamp:** *Anticipated Approval (November 2021)*
- **LED PAPI System:** *Anticipated Approval (March 2022)*
- **LED MALSR System:** *Anticipated Approval (August 2022)*

| Reasons for Change |
|--|
| <ul style="list-style-type: none">▪ LEDs▪ Changes in Standards▪ Color Boundaries▪ Photometrics▪ Changes in Testing Requirements▪ Design vs. Performance▪ Outdated Specifications |

Standard Installation Drawings


- Established a Working Group to update VGLS Standard Installation Drawings
 - Working Group members:
 - Civil and Electrical Engineers
 - WSA, CSA, ESA, HQ

Update Summary


- Outdated Drawings
- Changes in FAA Standards (i.e., FAA-STD-019)
- Improve Drawing Layout
- Outdated Specifications
- Comprehensive Drawing Package

Standard Installation Drawings

- Standard REIL Drawings approved 2018



- Standard PAPI Drawings approved 2019



Standard Installation Drawings


- MALSR Drawings are 75% complete
- Restarted MicroStation to AutoCAD conversion: September 2021
- Complete conversion from MicroStation to AutoCAD by January 2022
- Complete MALSR drawings by May 2022
- Complete remaining Drawings (ALSF-2 and any additional updates) by July 2022



[illegible]

Procurement Forecast

- ALSF-2 SLEP (FAA-E-2999)
- Incandescent PAR-38
- LED PAR-38/PAR-56
- RRCS
- SFSB



Note: You should monitor the <https://beta.sam.gov/> website for procurement opportunities.

Disclaimer: This forecast is for informational and marketing purposes only and does not constitute a specific offer or commitment by the FAA to fund in whole or in part any of the procurements referenced herein.

Questions?

